



**Date: February 25, 2026**  
**Proposal #2602-2501**

**Richard Bysice**  
**The Rhino Bar and Grill**  
+1 (905) 483-0460  
richard.bysice@therhino.ca

1249 Queen St W  
Toronto, ON M6K 1L5  
CANADA

**CyberQA Inc.**  
84 Barrington Ave.  
Toronto, ON  
M4C 4Z1 CANADA

+1(416) 520 1369  
pro@cyberqa.com  
www.cyberqa.com

BIN 705240612  
GST/HST account:

## Scope overview

CyberQA will remove the existing security gateway and three existing access points, supply and install new UniFi network equipment, and complete full system configuration to restore and optimize internet routing, Wi-Fi coverage, and management within the UniFi platform.

Pricing includes project mobilization and management, transportation, professional fees, insurance, and other project or deployment-related expenses.

### 1) Removal and disposal (existing equipment)

- Decommission and remove: 1 existing security gateway and 3 existing wireless access points
- Proper disconnection and jobsite cleanup

### 2) New equipment supply (UniFi)

- (1) Dream Machine Pro (UDM-Pro)
- (2) U7 Pro XG (U7-Pro-XG)
- (1) U7 Pro Outdoor (U7-Pro-Outdoor)

### **3) Installation and mounting**

- Physical installation of the UDM-Pro on the existing rack.
- Mounting and installation of three access points (2 indoor, 1 outdoor)
- Basic cable management and installation finishing

### **4) Configuration, commissioning, and system reconfiguration**

- Adopt and provision all new devices in UniFi
- Reconfigure the network system end-to-end (WAN/LAN setup as required)
- Configure wireless SSIDs, security, and optimization
- Apply updates/firmware alignment
- Validation testing for connectivity and performance

### **5) Installation accessories and incidentals**

- Mounting and fastening incidentals, cable dressing materials, and small consumables required to complete the installation cleanly and professionally

**Proposal total before tax**

**Total before HST: \$3,697.00**

### **Summary of what this proposal includes**

- Removal of the existing security gateway and three access points
- Supply of 1 UDM-Pro, 2 U7 Pro XG access points, and 1 U7 Pro Outdoor access point
- Installation and mounting of all new equipment (including outdoor AP)
- Full UniFi adoption, configuration, and complete system reconfiguration with testing
- Mobilization, project management, transportation, and required incidentals for delivery

## General Summary & Notes

- Client must provide access, washroom facilities, and dedicated power outlet.
- Does not include coring, fire stopping, conduits, wire moulds, or construction work; requires prior approval.
- **CyberQA Inc. provides 1-year labour warranty.**
- Ubiquiti hardware warranty handled through <https://rma.ui.com>.
- **Warranty-related equipment replacement labour is billable.**
- Tampering or relocating equipment voids warranty.
- No warranty on manufacturer software bugs or feature changes.
- Project insured through Zensurance Brokers Inc.
- **Services will be available in February/March 2026, subject to equipment availability and delivery lead times.**
- Terms: 60% deposit upfront, 40% upon completion.
- Quotation valid for 15 days.
- Performed by Ubiquiti Certified (UNS, UEWA) specialist.
- Cybersecurity best practices applied (Cybersecurity Certified - CC).
- CyberQA Inc. is Google 5-Star rated (<https://maps.app.goo.gl/gAN3XCGYvgHweMFx7>)
- CyberQA Inc. is a CANASA member.

### Accepted by Client:

Name: **Richard Bysice**

Date: \_\_\_\_\_

Signature: \_\_\_\_\_

### Accepted by CyberQA Inc.:

Name: **Taavi Tamtik**

Date: \_\_\_\_\_

Signature: \_\_\_\_\_