



Date: February 26, 2026
Proposal #2602-2601

Tommy Miles

Studio of Legends

+1 (647) 530-4063
tommym@studiooflegends.com

132 Jarvis St
Toronto, ON M5B 2B5
CANADA

CyberQA Inc.
84 Barrington Ave.
Toronto, ON
M4C 4Z1 CANADA

+1(416) 520 1369
pro@cyberqa.com
www.cyberqa.com

BIN 705240612
GST/HST account:

Scope overview

This pricing includes project mobilization, professional deployment labour, and deployment-related incidentals (accessories/fastening). All primary project materials and hardware are provided by the client, excluding standard installation incidentals as noted below.

Scope of Work

1) Data Cable Terminations (Cat6)

- Terminate 18 installed Cat6 cables: one end terminated to the rack patch panel and the second end terminated to keystone jack + wall plate.
- Include additional rack-side termination allowance to accommodate typical internal rack terminations and organization requirements.
- Basic testing and labeling/identification as part of closeout.

2) Video Cable Terminations (SDI / BNC)

- Terminate 10 installed SDI cables (both ends), totalling 20 BNC terminations.
- Basic continuity/signal verification.

3) Wireless Access Point Installation

- Install and mount 3 access points (client-provided hardware).

4) Network Equipment Mounting

- Mount 1 × UDM Pro.

- Mount 1 × 24-Port PoE Switch.
- Rack placement, securing, and basic physical organization.

5) Commissioning & Configuration

- 3 Hours – Commissioning & Configuration: System bring-up and operational verification, including initial device provisioning and integration. Basic network configuration to include VLAN segmentation, WLAN setup, cybersecurity hardening, firewall policy implementation, and Bell modem bypass configuration (where applicable). Final validation will include connectivity testing, performance verification, and confirmation of overall service readiness.

Pricing (Before Tax)

- Proposal Total (before HST): \$3,658

Summary of What This Proposal Includes

- Termination of installed Cat6 cabling to patch panel and outlets (keystone + wall plate).
- Termination of installed SDI cabling with BNC connectors on both ends.
- Installation of 3 access points.
- Mounting of UDM Pro and 24-Port PoE switch.
- 3 hours commissioning and configuration with validation/testing.
- Project mobilization and standard installation accessories/incidentals (fastening, small consumables).

General Summary & Notes

- Client must provide access, washroom facilities, and dedicated power outlet.
- Does not include coring, fire stopping, conduits, wire moulds, or construction work; requires prior approval.
- CyberQA Inc. provides 1-year labour warranty.
- Ubiquiti hardware warranty handled through <https://rma.ui.com>.
- Warranty-related equipment replacement labour is billable.

- Tampering or relocating equipment voids warranty.
- No warranty on manufacturer software bugs or feature changes.
- Project insured through Zensurance Brokers Inc.
- **Service availability in March 2026 is conditional upon the complete and timely provision of all client-supplied equipment, components, and installation accessories. Any delays, shortages, incompatibilities, or defects in client-provided materials may result in schedule adjustments without liability to CyberQA.**
- Terms: 60% deposit upfront, 40% upon completion.
- Quotation valid for 15 days.
- Performed by Ubiquiti Certified (UNS, UEWA) specialist.
- Cybersecurity best practices applied (Cybersecurity Certified - CC).
- CyberQA Inc. is Google 5-Star rated (<https://maps.app.goo.gl/gAN3XCGYvgHweMFx7>)
- CyberQA Inc. is a CANASA member.

Accepted by Client:

Name: **Tommy Miles**

Date: _____

Signature: _____


Accepted by CyberQA Inc.:

Name: **Taavi Tamtik**

Date: _____

Signature: _____